



020337000

System Application

Becker County Planning & Zoning
915 Lake Ave, Detroit Lakes, MN 56501
Phone (218)-846-7314; Fax (218)-846-7266


PARCEL	
APP	SEPTIC
YEAR	
SCANNED	
LAKE	

1. PROPERTY DATA (as it appears on the tax statement, purchase agreement or deed)

Parcel Number(s) of property where the system will be installed: 020337000

Is this a split of an existing property? Yes No

(If yes and a parcel number has not yet been assigned, indicate the main parcel number from which the new parcel was split.)



Section 32 Township 139 Range 42 Township Name Andabon

Lake Name Little Cormorant Lake Classification _____

Legal Description: 1st Add to Sugar Island Block 1 Lot 3

Project Address: 16431 Sugar Island Rd.

2. PROPERTY OWNER INFORMATION (as it appears on the tax statement, purchase agreement or deed)

Owner's First Name Jeffrey Owner's Last Name Campbell

Mailing Address 16431 Sugar Island Rd. City, State, Zip Andabon Mn

Phone Number _____

3. DESIGNER/INSTALLER INFORMATION

Designer Name Rick Renner Company Name Renner Exc. LLC License # 2567

Address Andabon Mn. Phone Number 439-3514

Installer Name Same Company Name _____ License # _____

Address _____ Phone Number _____

4. SYSTEM DESIGN INFORMATION

System Status

What will new system serve? Check one

- Vacant Lot-No existing system-new structure
- Replacement - structure removed and being rebuilt
- Failing -Replacement- cesspool/seepage pit or other
- Enlargement of system-Undersized
- Repairs Needed to existing
- Additional system on property

- Dwelling
- Resort/Commercial
- Commercial (Non-resort)
- Other - explain below _____

7-27-12 Date of site evaluation

Design Flow 600 Gallons Per Day

Number of Bedrooms 4

Garbage Disposal Yes No

Dishwasher Yes No

Lift station in House Yes No

Grinder pump in House Yes No

Well Depth >50'

Depth of other wells within _____

100 ft of system _____

Original Soil _____ Compacted Soil _____

Type of Soil Observation _____

Pit Probe Boring

Depth to Restricting Layer _____

Maximum Depth of System _____

Size of All Tanks to be installed

1000 gal Single Compartment Septic Tank _____ gal Separate Lift Station

_____ gal Compartmented Tank _____ gal Holding Tank

_____ Pit Privy _____ Existing Tank to be used

_____ Existing tank w/new Additional Tank

_____ Existing tank w/new Lift Station

_____ Holding Tank with Privy

Total Number of tanks to be installed in this system 1 (This # will be reported to MPCA at end of year.)

PARCEL	
APP	SEPTIC
YEAR	

Type of Drainfield _____ Full Size of Drainfield _____ sq ft Reduced/Warrantied size _____ sq ft

_____ Chamber Trench _____ sq ft _____ sq ft

_____ Rock Trench _____ sq ft _____ sq ft

_____ Gravelless _____ sq ft _____ sq ft

_____ Mound _____ sq ft ***

_____ Pressure Bed _____ sq ft ***

_____ Seepage Bed _____ sq ft ***

_____ At-grade _____ sq ft ***

_____ Alternative / _____ sq ft *** *** Attach Worksheets

Performance

Type of chamber _____

Depth of Rock _____

Alarm? Yes _____ No _____

Type of Alarm _____

Size of Lift Pump _____

Size of Lift Line _____

Distance to Well _____

Distance to Building _____

Distance to Property Line _____

Distance to OHW of Lake _____

Distance to Pressure Line _____

Distance to Wetland/Protected Water _____

PROPOSED SETBACKS	
TANK	DRAINFIELD
60'	
14'	
10'	
85'	
40'	

Replacing septic tank only!

Perc Rate _____ Soil Sizing Factor _____ *If SSF other than .83, attach Perc Test Data

Soil Borings (three are required)

Depth	Texture	Color	Structure		Depth	Texture	Color	Structure

Depth	Texture	Color	Structure		Depth	Texture	Color	Structure

5. REQUIRED DOCUMENTS

U of MN worksheets are required for mounds, pressure beds, seepage beds, at-grades or Type IV or Type V systems. Are the required worksheets attached? _____ Yes _____ No

6. DESIGNER'S CERTIFIED STATEMENT

I, Rick Renner certify that I have completed the preceding design work in accordance with all applicable requirements (including, but not limited to Minnesota Chapter 7080 and the Becker County Individual Sewage Treatment System Ordinance).


Rick Renner
Signature of Designer

8-9-12
Date


SKETCH OF PROPERTY

Please sketch all structures and septic systems on the property;
Include setbacks and wells within 100 feet of the property.

PARCEL	
APP	SEPTIC
YEAR	2012



Sugar Island Row





COUNTY OF BECKER

Planning and Zoning

915 Lake Ave, Detroit Lakes, MN 56501

Phone: 218-846-7314 ~ Fax: 218-846-7266

SSTS STATEMENT - # OF BEDROOMS AND WATER-USE APPLIANCES

Note: Form must be legible and completed in ink

Property Owner Name(s): _____

Address: _____ City, State, Zip: _____

Phone: _____ Alt. Phone: _____

Legal Description: _____

Lake/River: _____ Tax Parcel No. _____

Property Address: _____

Definitions:

Bedroom – any room or unfinished area within a dwelling that might reasonably be used as a sleeping room. Lofts and unfinished basements (with at least one egress window and/or door) are counted as bedrooms.

Water-use Appliances – installed or anticipated: e.g. automatic washer, dishwasher, water conditioning unit, whirlpool bath, garbage disposal, or self-cleaning humidifier in furnace.

Note: A dishwasher with a built-in garbage disposal counts as two (2) water-use appliances.

Existing # of bedrooms: 4 + # of bedrooms yet to be constructed: _____ = Total # of bedrooms to be serviced by the SSTS: _____ (min. # bedrooms allowed by State is two)

Existing # of water-use appliances: _____ List each: 3 toilet dishwasher
+ # of water-use appliances yet to be installed: _____ List each: _____
_____ = Total # of water-use appliances to be serviced by the SSTS: _____

I (we) do hereby swear and affirm that the above-stated number of bedrooms and water-use appliances exist and/or will be installed in the residence located on the property listed on this document such that they will be serviced by the subsurface sewage treatment system (SSTS) that will be designed for and connected to said residence and installed on said property.

Jeffrey A. [Signature]
Property Owner(s) Signature(s)

8/20/12
Date

Application Approved by: Heidi Maltz Date: 8-13-12
Amount Paid 15000 Receipt Number 5287607 Permit Number _____

NOTES: 511733

INSPECTION REPORT

Home Information

Does the structure contain any of the following elements?

Garbage disposer Yes No Dishwasher Yes No
Grinder pump Yes No Lift pump in basement Yes No
Effluent screen installed? Yes No Effluent screen manufacturer _____

Alarm required? Yes No Alarm Type _____ Alarm manufacturer _____

Lift pump in system? Yes No Pump manufacturer _____

Number of bedrooms 4

Component Information

Tank size 1000 Plastic Tank manufacturer Infiltrator

Drainfield size _____
Drainfield medium _____ Medium manufacturer _____
Drainfield medium size/depth _____

Soil Verification

Vertical separation verified for Boring #1 on _____ Depth _____
Vertical separation verified for Boring #2 on _____ Depth _____
Vertical separation verified for Boring #3 on _____ Depth _____

TANK only

Setback Verification

	TANK	DRAINFIELD
Distance to Well	<u>60</u>	_____
Distance to Building	<u>14</u>	_____
Distance to Property Line	<u>10</u>	_____
Distance to OHW of Lake	<u>85</u>	_____
Distance to Pressure Line	<u>40</u>	_____
Distance to Wetland/Protected Water	<u>N/A</u>	_____

Date System Installed 8/20/12 Installer R. Renner Exc. Inspector Jane Stoll

CERTIFICATE OF COMPLIANCE

() Certificate Is Hereby Denied
(X) Certificate is Hereby Granted Based upon the Application, addendum from, plans, specifications and all other supporting data.
With property maintenance, this system can be expected to function satisfactory, however, this is not a guarantee.

Signature Jane Stoll Title JTS Inspector Date 8/20/12

(Certificate of Compliance is not valid unless signed by a Registered Qualified Employee)





Minnesota Pollution Control Agency

520 Lafayette Road North
St. Paul, MN 55155-4194

Compliance Inspection Form

Existing Subsurface Sewage Treatment Systems (SSTS)

Doc Type: Compliance and Enforcement

Instructions: Inspection results based on Minnesota Pollution Control Agency (MPCA) requirements and attached forms – additional local requirements may also apply.

Submit completed form to Local Unit of Government (LUG) and system owner within 15 days

For local tracking purposes:

System Status

System status on date (mm/dd/yyyy): 8-15-12

Compliant – Certificate of Compliance
(Valid for 3 years from report date, unless shorter time frame outlined in Local Ordinance.)

Noncompliant – Notice of Noncompliance
(See Upgrade Requirements on page 3)

Reason(s) for noncompliance (check all applicable)

- Impact on Public Health (Compliance Component #1) – Imminent threat to public health and safety
- Other Compliance Conditions (Compliance Component #3) – Imminent threat to public health and safety
- Tank Integrity (Compliance Component #2) – Failing to protect groundwater
- Other Compliance Conditions (Compliance Component #3) – Failing to protect groundwater
- Soil Separation (Compliance Component #4) – Failing to protect groundwater
- Operating permit/monitoring plan requirements (Compliance Component #5) – Noncompliant

Property Information

Parcel ID# or Sec/Twp/Range: 020337000

Property address: 16431 Sugar Island Rd.

Reason for inspection: County Request

Property owner: Jeff Campbell

Owner's phone: _____

or

Owner's representative: _____

Representative phone: _____

Local regulatory authority: Becker Co zoning

Regulatory authority phone: 846-7314

Brief system description: 1000 gal Septic tank, 500 gal pump tank, 450 sq ft.

Comments or recommendations: Mound,

Certification

I hereby certify that all the necessary information has been gathered to determine the compliance status of this system. No determination of future system performance has been nor can be made due to unknown conditions during system construction, possible abuse of the system, inadequate maintenance, or future water usage.

Inspector name: Rick Renner

Certification number: _____

Business name: Renner Exc. LLC.

License number: 2567

Inspector signature: Rick Renner

Phone number: 218-439-3514

Necessary or Locally Required Attachments


- Soil boring logs
- System/As-built drawing
- Forms per local ordinance
- Other information (list): _____

SKETCH OF PROPERTY

PARCEL	
APP	SITE
YEAR	2011

1. Please sketch all structures on the property; include setbacks
And wells within 100 feet of the property.
-

See Permit App



Remember EROSION CONTROL!

Please use best management practices and/or silt fence to control erosion on all projects.

Property address: 020337000

Inspector initials/Date: RR 8-15-12

1. Impact on Public Health – Compliance component #1 of 5

Compliance criteria:

System discharge sewage to the ground surface.	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
System discharge sewage to drain tile or surface waters.	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
System cause sewage backup into dwelling or establishment.	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No

Any "yes" answer above indicates the system is an Imminent Threat to Public Health and Safety.

Comments/Explanation:

Verification method(s):

- Searched for surface outlet
- Searched for seeping in yard/backup in home
- Excessive ponding in soil system/D-boxes
- Homeowner testimony (See Comments/Explanation)
- "Black soil" above soil dispersal system
- System requires "emergency" pumping
- Performed dye test
- Unable to verify (See Comments/Explanation)
- Other methods not listed (See Comments/Explanation)

2. Tank Integrity – Compliance component #2 of 5

Compliance criteria:

System consists of a seepage pit, cesspool, drywell, or leaching pit. <i>Seepage pits meeting 7080.2550 may be compliant if allowed in local ordinance.</i>	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
Sewage tank(s) leak below their designed operating depth. If yes, which sewage tank(s) leaks:	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No

Any "yes" answer above indicates the system is Failing to Protect Groundwater.

Comments/Explanation:

Verification method(s):

- Probed tank(s) bottom
- Examined construction records
- Examined Tank Integrity Form (Attach)
- Observed liquid level below operating depth
- Examined empty (pumped) tanks(s)
- Probed outside tank(s) for "black soil"
- Unable to verify (See Comments/Explanation)
- Other methods not listed (See Comments/Explanation)

3. Other Compliance Conditions – Compliance component #3 of 5

- a. Maintenance hole covers are damaged, cracked, unsecured, or appear to structurally unsound. Yes* No Unknown
- b. Other issues (electrical hazards, etc.) to immediately and adversely impact public health or safety. Yes* No Unknown
***System is an imminent threat to public health and safety**

Explain:

- c. System is non-protective of ground water for other conditions as determined by inspector Yes* No
***System is failing to protect groundwater**

Explain:

4. Soil Separation – Compliance component #4 of 5

Date of installation: _____ Unknown
 Shoreland/Wellhead protection/Food Beverage Lodging? Yes No

Verification method(s):

Soil observation does not expire. Previous soil observations by two independent parties are sufficient, unless site conditions have been altered or local requirements differ.

- Conducted soil observation(s) (Attach boring logs)
- Two previous verifications (Attach boring logs)
- Not applicable (Holding tank(s), no drainfield)
- Unable to verify (See Comments/Explanation)
- Other (See Comments/Explanation)

Compliance criteria:

For systems built prior to April 1, 1996, and not located in Shoreland or Wellhead Protection Area or not serving a food, beverage or lodging establishment: Yes No
 Drainfield has at least a two-foot vertical separation distance from periodically saturated soil or bedrock.

Non-performance systems built April 1, 1996, or later or for non-performance systems located in Shoreland or Wellhead Protection Areas or serving a food, beverage, or lodging establishment: Yes No
 Drainfield has a three-foot vertical separation distance from periodically saturated soil or bedrock.*

Comments/Explanation:

mound clay soil

"Experimental", "Other", or "Performance" systems built under pre-2008 Rules; Type IV or V systems built under 2008 Rules (7080.2350 or 7080.2400 (Advanced Inspector License required) Yes No
 Drainfield meets the designed vertical separation distance from periodically saturated soil or bedrock.

Indicate depths of elevations

A. Bottom of distribution media	3'
B. Periodically saturated soil/bedrock	7' +
C. System separation	4'
D. Required compliance separation*	3'

*May be reduced up to 15 percent if allowed by Local Ordinance.

Any "no" answer above indicates the system is Failing to Protect Groundwater.

5. Operating Permit and Nitrogen BMP* – Compliance component #5 of 5 Not applicable

Is the system operated under an Operating Permit? Yes No If "yes", A below is required
 Is the system required to employ a Nitrogen BMP? Yes No If "yes", B below is required

BMP=Best Management Practice(s) specified in the system design

If the answer to both questions is "no", this section does not need to be completed.

Compliance criteria

- a. Operating Permit number: _____ Yes No
 Have the Operating Permit requirements been met?
- b. Is the required nitrogen BMP in place and properly functioning? Yes No

Any "no" answer indicates Noncompliance.

Upgrade Requirements (Minn. Stat. § 115.55) An imminent threat to public health and safety (ITPHS) must be upgraded, replaced, or its use discontinued within ten months of receipt of this notice or within a shorter period if required by local ordinance. If the system is failing to protect ground water, the system must be upgraded, replaced, or its use discontinued within the time required by local ordinance. If an existing system is not failing as defined in law, and has at least two feet of design soil separation, then the system need not be upgraded, repaired, replaced, or its use discontinued, notwithstanding any local ordinance that is more strict. This provision does not apply to systems in shoreland areas, Wellhead Protection Areas, or those used in connection with food, beverage, and lodging establishments as defined in law.

**PERMIT MUST BE
POSTED AT THE
CONSTRUCTION SITE**

Becker County Planning & Zoning
835 Lake Ave, P O Box 787
Detroit Lakes, MN 56502-0787
Phone (218)-846-7314; Fax (218)-846-7266

Onsite Septic System Site Evaluation/Design

Tax Parcel Number 02.0337.000

Legal Description: Lot 3 Block 1 1st Add to Sugar Island Section 32 TWP 139 Range 42
Fire Number _____

Lake Name Little Cormorant Lake Classification RD Township Name Audubon

Owner's Name Robert Weichert Address 16431 Sugar Island

City Audubon MN State/Zip 56511 Phone Number _____

Number of Bedrooms 4 Well Casing Depth deep Garbage Disposal (Yes) (No)
Design Flow 600 GPD Depth of other Wells within 100 ft of system N/A Grinder Pump/Lift Station In House (Yes) (No)

Type of Observation: Probe Pit Boring
Original Soil (Yes) (No) Compacted Soil (Yes) (No)
Depth to Restricting Layer 2.5' Proposed Design
Maximum of Depth of System mound () Replace Septic Tank
Perc Rate 18.5 Soil Sizing Factor _____ () Septic Tank/Drainfield
() Drainfield Only
() Holding Tank
 Lift Station Type of Drainfield
() Standard (gravelless/chamber)
() Standard (rock depth _____)
() Standard Bed
 Mound () At Grade
() Pressurized Bed

SOIL BORING LOG

DEPTH (INCHES)	TEXTURE	COLOR & MUNSELL NO.	STRUCTURE
0-10	CLAY	S, 11	BLOCKY PLATY PRISMATIC NONE
10-18	10AM	Topsoil	BLOCKY PLATY PRISMATIC NONE
18-34	CLAY 10AM	2.5Y 4/3	BLOCKY PLATY PRISMATIC NONE
34-48	" "	2.5Y 4/4	BLOCKY PLATY PRISMATIC NONE
48-60	silt	2.5Y 4/3	BLOCKY PLATY PRISMATIC NONE

SOIL BORING LOG

DEPTH (INCHES)	TEXTURE	COLOR & MUNSELL NO.	STRUCTURE
0-10	CLAY to be removed	S, 11	BLOCKY PLATY PRISMATIC NONE
10-20	10AM	Topsoil	BLOCKY PLATY PRISMATIC NONE
20-28	CLAY	10YR 3/4	BLOCKY PLATY PRISMATIC NONE
28-44	silt clay	10YR 7/4	BLOCKY PLATY PRISMATIC NONE
44-60	silt	2.5Y 5/2	BLOCKY PLATY PRISMATIC NONE

Attach Perc Test Information If Required

Name and Address of Designer Randy Anderson P.O. box 1421 Detroit Lakes Phone 849-3072

MPCA Number 1034 Date of Site Evaluation 5.11.99 Signature of Designer [Signature]

Name of Installer (if different from Designer) _____ MPCA Number _____

FOR USE BY BECKER COUNTY ENVIRONMENTAL SERVICES DEPARTMENT ONLY

- *** Any changes to the permit must first be approved by Becker County Planning & Zoning. No system shall be covered up without inspection by Becker County Planning & Zoning.
- *** Inspections must be scheduled at least 24 hours prior to time requested.

Date Received 5/14/99 Application Fee 75⁰⁰ State Surcharge 150 Total 75⁵⁰


[] Application is hereby denied
 Application is hereby granted to R. Weichert to install an individual septic system according to the specifications of the site evaluation and design submitted to the Becker County Environmental Services Office. By Order of: [Signature]

Signature of Becker County Qualified Employee [Signature] Date Permit Issued 5/14/99 Permit Number 13302
 This permit expires on 5/14/00

The site plan must be drawn to dimension or to scale:

- *Dimensions of Lot
- *Existing & Proposed Buildings
- *Easements & setbacks
- *Well & Water Line Locations
- *Distance from Property Lines
- *Tank Access Route
- within 100 ft of System
- *Distance from Ordinary High Water
- *Distance from buildings

- *Scale - One inch = _____ ft
- *Location of any Unsuitable Soil
- *Soil Borings & Per Test Locations
- *Alternate Drainfield Location



	Twp Road				
	Tank (estimated)	Tank (actual)	Drainfield (estimated)	Drainfield (actual)	
Distances to Well	_____	_____	_____	_____	Tank size _____
Distance to Building	_____	_____	_____	_____	Lift station size _____
Distance to Property Line	_____	_____	_____	_____	Drainfield size _____
Distance to Pressure Line	_____	_____	_____	_____	Pump HP _____
Distance to Ordinary High Water	_____	_____	_____	_____	Date Installed _____

FOR USE BY BECKER COUNTY ENVIRONMENTAL SERVICES DEPARTMENT ONLY

CERTIFICATE OF COMPLIANCE

() Certificate Is Hereby Denied
 (✓) Certificate is Hereby Granted Based upon the Application, addendum from, plans, specifications and all other supporting data. With property maintenance, this system can be expected to function satisfactory, however, this is not a guarantee.

Signature _____ Title Inspector Date 10 June 99

(Certificate of Compliance is not valid unless signed by a Registered Qualified Employee)

- PERCOLATION TEST SHEET -

Test hole location Proposed Drainfield Hole # 2 Date test hole was prepared: 5.10.99

Depth of hole bottom: 12 inches Diameter of hole: 6 inches

Soil Data from test hole:

depth, inches	soil texture:	soil color:
<u>0-12</u>	<u>10AM</u>	<u>Tp 250.1</u>

Method of scratching sidewall: WIRE Depth of pea size gravel in bottom of hole: 12 inches

Date and hour of initial water filling: 5.10.99 Depth of initial water filling: 12 above hole bottom

Method used to maintain 12" of water depth in hole for 4 hours: MANUAL

Percolation test conducted by: Randy Anderson Percolation test started at _____ (am / pm).

Maximum water depth above hole bottom during test: 8 inches

TIME	INTERVAL (MINUTES)	WATER DEPTH	WATER DROP (fraction)	WATER DROP (decimal)	PERC RATE CALCULATION	conversions
---	START <u>17.5</u>	<u>8</u> ---	---	---	$\frac{17.5}{\text{TIME}} \div \frac{1}{\text{DROP}} = \frac{17.5}{\text{PERC}}$ A	1/16 = .06
---	REFILL <u>19</u>	<u>8</u> ---	<u>1</u> ---	<u>1</u> ---	$\frac{19}{\text{TIME}} \div \frac{1}{\text{DROP}} = \frac{19}{\text{PERC}}$ B	1/8 = .13
---	REFILL <u>18.75</u>	<u>8</u> ---	<u>1</u> ---	<u>1</u> ---	$\frac{18.75}{\text{TIME}} \div \frac{1}{\text{DROP}} = \frac{18.75}{\text{PERC}}$ C	3/16 = .19
---	REFILL	---	---	---	$\frac{\text{---}}{\text{TIME}} \div \frac{\text{---}}{\text{DROP}} = \frac{\text{---}}{\text{PERC}}$ D	1/4 = .25
---	REFILL	---	---	---	$\frac{\text{---}}{\text{TIME}} \div \frac{\text{---}}{\text{DROP}} = \frac{\text{---}}{\text{PERC}}$ E	5/16 = .31
---	REFILL	---	---	---	$\frac{\text{---}}{\text{TIME}} \div \frac{\text{---}}{\text{DROP}} = \frac{\text{---}}{\text{PERC}}$ F	3/8 = .38
---	REFILL	---	---	---	$\frac{\text{---}}{\text{TIME}} \div \frac{\text{---}}{\text{DROP}} = \frac{\text{---}}{\text{PERC}}$ G	7/16 = .44
---	REFILL	---	---	---	$\frac{\text{---}}{\text{TIME}} \div \frac{\text{---}}{\text{DROP}} = \frac{\text{---}}{\text{PERC}}$ H	1/2 = .5
---	REFILL	---	---	---	$\frac{\text{---}}{\text{TIME}} \div \frac{\text{---}}{\text{DROP}} = \frac{\text{---}}{\text{PERC}}$	9/16 = .56
---	REFILL	---	---	---	$\frac{\text{---}}{\text{TIME}} \div \frac{\text{---}}{\text{DROP}} = \frac{\text{---}}{\text{PERC}}$	5/8 = .63
---	REFILL	---	---	---	$\frac{\text{---}}{\text{TIME}} \div \frac{\text{---}}{\text{DROP}} = \frac{\text{---}}{\text{PERC}}$	11/16 = .69
---	REFILL	---	---	---	$\frac{\text{---}}{\text{TIME}} \div \frac{\text{---}}{\text{DROP}} = \frac{\text{---}}{\text{PERC}}$	3/4 = .75
---	REFILL	---	---	---	$\frac{\text{---}}{\text{TIME}} \div \frac{\text{---}}{\text{DROP}} = \frac{\text{---}}{\text{PERC}}$	13/16 = .81
---	REFILL	---	---	---	$\frac{\text{---}}{\text{TIME}} \div \frac{\text{---}}{\text{DROP}} = \frac{\text{---}}{\text{PERC}}$	7/8 = .88
---	REFILL	---	---	---	$\frac{\text{---}}{\text{TIME}} \div \frac{\text{---}}{\text{DROP}} = \frac{\text{---}}{\text{PERC}}$	15/16 = .94

Ten Percent Calculation *

A, B, C

Largest # of ABC - Smallest # of ABC = _____

Smallest # of ABC x 0.10 = _____

C, D, E

Largest # of CDE - Smallest # of CDE = _____

Smallest # of CDE x 0.10 = _____

E, F, G

Largest # of EFG - Smallest # of EFG = _____

Smallest # of EFG x 0.10 = _____

B, C, D

Largest # of BCD - Smallest # of BCD = _____

Smallest # of BCD x 0.10 = _____

D, E, F

Largest # of DEF - Smallest # of DEF = _____

Smallest # of DEF x 0.10 = _____

F, G, H

Largest # of FGH - Smallest # of FGH = _____

Smallest # of FGH x 0.10 = _____

* If the top number in each set of boxes is larger than the bottom number then take another reading. If the top number is equal or smaller than bottom number, average the three numbers for the perc rate.

- PERCOLATION TEST SHEET -

Test hole location Proposed Drain Field Hole # 1 Date test hole was prepared: 5.10.99
 Depth of hole bottom: 12 inches Diameter of hole: 6 inches
 Soil Data from test hole:

depth, inches	soil texture:	soil color
<u>0-10</u>	<u>CLAY fill to be removed</u>	<u>Topsoil</u>
<u>10-22</u>	<u>LOAM</u>	<u>Topsoil</u>

Method of scratching sidewall: WIRE Depth of pea size gravel in bottom of hole: 12 inches
 Date and hour of initial water filling: 5.10.99 Depth of initial water filling: 8 above hole bottom
 Method used to maintain 12" of water depth in hole for 4 hours: MANUAL
 Percolation test conducted by: Randy Anderson Percolation test started at _____ (am / pm).
 Maximum water depth above hole bottom during test: _____ inches

TIME	INTERVAL (MINUTES)	WATER DEPTH	WATER DROP (fraction)	WATER DROP (decimal)	PERC RATE CALCULATION	conversions
---	START	<u>8</u>	---	---	$\frac{16}{\text{TIME}} \div \frac{1}{\text{DROP}} = \frac{16}{\text{PERC}}$ A	1/16 = .06
---	<u>16</u>	<u>7</u>	<u>1</u>	<u>1</u>		1/8 = .13
---	REFILL	<u>8</u>	---	---	$\frac{16.5}{\text{TIME}} \div \frac{1}{\text{DROP}} = \frac{16.5}{\text{PERC}}$ B	3/16 = .19
---	<u>16 1/2</u>	<u>7</u>	<u>1</u>	<u>1</u>		1/4 = .25
---	REFILL	<u>8</u>	---	---	$\frac{17}{\text{TIME}} \div \frac{1}{\text{DROP}} = \frac{17}{\text{PERC}}$ C	5/16 = .31
---	<u>17</u>	<u>7</u>	<u>1</u>	<u>1</u>		3/8 = .38
---	REFILL	-----	-----	-----	$\frac{\text{TIME}}{\text{DROP}} = \text{PERC}$ D	7/16 = .44
---	-----	-----	-----	-----		1/2 = .5
---	REFILL	-----	-----	-----	$\frac{\text{TIME}}{\text{DROP}} = \text{PERC}$ E	9/16 = .56
---	-----	-----	-----	-----		5/8 = .63
---	REFILL	-----	-----	-----	$\frac{\text{TIME}}{\text{DROP}} = \text{PERC}$ F	11/16 = .69
---	-----	-----	-----	-----		3/4 = .75
---	REFILL	-----	-----	-----	$\frac{\text{TIME}}{\text{DROP}} = \text{PERC}$ G	13/16 = .81
---	-----	-----	-----	-----		7/8 = .88
---	REFILL	-----	-----	-----	$\frac{\text{TIME}}{\text{DROP}} = \text{PERC}$ H	15/16 = .94
---	-----	-----	-----	-----		

Ten Percent Calculation *

A, B, C

Largest # of ABC - Smallest # of ABC = _____

Smallest # of ABC x 0.10 = _____

C, D, E

Largest # of CDE - Smallest # of CDE = _____

Smallest # of CDE x 0.10 = _____

E, F, G

Largest # of EFG - Smallest # of EFG = _____

Smallest # of EFG x 0.10 = _____

B, C, D

Largest # of BCD - Smallest # of BCD = _____

Smallest # of BCD x 0.10 = _____

D, E, F

Largest # of DEF - Smallest # of DEF = _____

Smallest # of DEF x 0.10 = _____

F, G, H

Largest # of FGH - Smallest # of FGH = _____

Smallest # of FGH x 0.10 = _____

* If the top number in each set of boxes is larger than the bottom number then take another reading. If the top number is equal or smaller than bottom number, average the three numbers for the perc rate.

MOUND DESIGN WORKSHEET

(For Flows up to 1200 gpd)

A. FLOW

Estimated 600 gpd
 or measured _____ x 1.5 = _____ gpd.

Estimated Sewage Flows in Gallons per day (gpd)

Number of Bedrooms	Type I	Type II	Type III	Type IV
2	300	225	180	60% of the values in Type I, II or III columns
3	450	300	218	
4	600	375	256	
5	750	450	294	
6	900	525	332	
7	1050	600	370	
8	1200	675	408	

B. SEPTIC TANK LIQUID VOLUMES

1000 gallons

C. SOILS (refer to site evaluation)

1. Depth to restricting layer = 34 inches _____ feet
2. Depth of percolation tests = 12 inches
3. Texture LOAM Percolation rate 18 mpi
4. Land slope 0-1 %

Septic Tank Capacities (in gallons)


Number of Bedrooms	Minimum Liquid Capacity	Liquid capacity with garbage disposal
2 or less	750	1125
3 or 4	1000	1500
5 or 6	1500	2250
7, 8 or 9	2000	3000

D. ROCK LAYER DIMENSIONS

1. Multiply flow rate by 0.83 to obtain required area of rock layer: $A \times 0.83 =$
 $\frac{600}{\text{gpd}} \times 0.83 \text{ sq. ft./gpd} = \underline{500} \text{ sq. ft.}$
2. Select width of rock layer (max 10' if <120 mpi max 5') = 10 ft.
3. Length of rock layer = area ÷ width =
 $\frac{500 \text{ sq. ft.}}{10 \text{ ft.}} = \underline{50} \text{ ft.}$



Width 10 ft
 <120mpi <10'
 >120mpi <5'



Length 50 ft

E. ROCK VOLUME

1. Multiply rock area by rock depth to get cubic feet of rock; _____ sq. ft. x _____ ft. = 500 cu. ft.
2. Divide cu. ft. by 27 cu. ft./cu. yd. to get cubic yards;
 _____ cu. ft. ÷ 27 = 18.5 cu. yd.
3. Multiply cubic yards by 1.4 to get weight of rock in tons; _____ cu. yd. x 1.4 ton/cu. yd. = 26 tons.

CLEAN SAND APPROX 40 cu. yds

F. ABSORPTION WIDTH

1. Percolation rate in top 12 inches of soil is _____ mpi
 Texture _____
2. Select allowable soil loading rate from table;
 _____ gpd/ft²
3. Calculate adsorption width ratio by dividing rock layer loading rate of 1.20 gpd/ft² by allowable soil loading rate;

Absorption Width Sizing Table

Percolation Rate in Minutes per Inch (MPI)	Soil Texture	Gallons per day per square foot	Ratio of Absorption width to Rock Layer Width
Faster than 0.1	Coarse Sand	1.20	1.00
0.1 to 5	Sand	1.20	1.00
0.1 to 5	Fine Sand	0.60	2.00
6 to 15	Sandy Loam	0.79	1.52
16 to 30	Loam	0.60	2.00
31 to 45	Silt Loam	0.50	2.40
46 to 60	Clay Loam	0.45	2.67
60 to 120	Clay	0.24	5.00
Slower than 120	Clay	0.20	6.00

loading rate of 1.20 gpd/ft² by allowable soil loading rate;
 $1.20 \text{ gpd/ft}^2 \div \text{_____ gpd/ft}^2 = \text{_____}$

4. Multiply adsorption width ratio by rock layer width to get required adsorption width;

$\underline{10} \times \underline{2.4} \text{ ft} = \underline{24} \text{ ft}$



BECKER COUNTY

829 LAKE AVENUE, P.O. BOX 787
 DETROIT LAKES, MINNESOTA 56502-0787
 (218) 846-7314

SKETCH PLAN FORM H

Fire No.
Application No.
Tax Parcel No.

Please be as complete as possible. Include all of the items listed below where applicable.

GENERAL CHECKLIST

- scale
- north arrow
- lot dimensions
- structure location
- side lot setback
- road setback
- septic tank location
- drainfield location
- location of all wells within 100' of drainfield
- fill & grading limits
- vegetation alteration limits

WATER RESOURCE CHECKLIST

- location of ordinary high water level (OHWL)
- location of present water line
- setback from OHWL
- location of highest known water level
- existing local drainage
- location of wetland areas

Scale of Diagram: 1 inch = _____ feet

Drawing By: _____

Date of Drawing: _____

Remarks: _____


Bob Weinert

Commonwealth Lake. Install New Drain Field

Signature _____

Edwin Jander

11-10-94





BECKER COUNTY

829 LAKE AVENUE, P.O. BOX 787
 DETROIT LAKES, MINNESOTA 56502-0787
 (218) 846-7314

Fire No.
Application No.
Tax Parcel No.

SKETCH PLAN FORM H

Please be as complete as possible. Include all of the items listed below where applicable.

GENERAL CHECKLIST

- scale
- north arrow
- lot dimensions
- structure location
- side lot setback
- road setback
- septic tank location
- drainfield location
- location of all wells within 100' of drainfield
- fill & grading limits
- vegetation alteration limits

WATER RESOURCE CHECKLIST

- location of ordinary high water level (OHWL)
- location of present water line
- setback from OHWL
- location of highest known water level
- existing local drainage
- location of wetland areas


Scale of Diagram: 1 inch = _____ feet

Drawing By: _____

Date of Drawing: _____


Remarks: Bob Weinert

Signature _____



PRESSURE DISTRIBUTION SYSTEM

- Select number of perforated laterals 3
- Select perforation spacing = 3.5 feet.
- Since perforations should not be placed closer than 1 ft. to the edge of the rock layer (see diagram), subtract 2 ft. from the rock layer length.



Perf Sizing 7/32" - 1/4"
Perf Spacing 1.5' - 5'

$$\frac{50}{\text{Rock layer length}} - 2 \text{ ft.} = \underline{48} \text{ feet.}$$

- Determine the number of spaces between perforations. Divide the length above by perforation spacing and round down to nearest whole number.

$$\text{Length perf. spacing} = \frac{48}{(3)} \text{ ft.} \div \frac{3.5}{(2)} \text{ ft.} = \underline{14} \text{ spaces}$$

- Number of perforations is equal to one plus the number of perforation spaces.

$$\underline{14} \text{ spaces} + 1 = \underline{15} \text{ perforations/lateral}$$

- Multiply perforations per lateral by number of laterals to get total number of perforations.

$$\frac{3}{\text{laterals}} \times \frac{15}{\text{perfs/lateral}} = \underline{45} \text{ perforations.}$$

- Determine required flow rate by multiplying number of perforations by flow per perforation

$$\frac{45}{\text{perfs}} \times \frac{124}{\text{gpm/perf}} = \underline{33} \text{ gpm.}$$


- If laterals are connected to header pipe as shown on upper example, to select minimum required lateral diameter; enter table with perforation spacing and number of perforations per lateral. Select minimum diameter for perforated lateral = 1.5 inches.

Required Perforation Discharge in gallons per minute (gpm)		
Discharge Head (feet)	3/32" each perf	1/4" each perf
1.0a	0.56	0.74
2.0b	0.80	1.04


a. Use for single family homes
b. Use for all other applications

Maximum number of quarter inch perforations per lateral to guarantee < 10% discharge variation			
Perforation Spacing (feet)	1 1/4	1 1/2	2
2.5	14	18	28
3.0	13	17	26
3.3	12	16	25
4.0	11	15	23
5.0	10	14	22

MANIFOLD LOCATED AT END OF PRESSURE DISTRIBUTION SYSTEM



LAYOUT OF PERFORATED PIPE LATERALS FOR PRESSURE DISTRIBUTION IN MOUND



- pump specs 33 gpm At 14' of Head*
- If perforated lateral system is attached to manifold pipe near the center, lower diagram, perforated lateral length and number of perforations per lateral will be approximately one half of that in step 8. Using these values, select minimum diameter for perforated lateral = _____ inches.

G. DOWNSLOPE BERM WIDTH

1. If landslope is 1% or more, subtract rock layer width from adsorption width to obtain minimum downslope berm toe
 ft - ft = feet

2. Calculate Minimum mound Size
 a. Determine depth of clean sand fill at upslope edge of rock layer:
 Separation 3' - 2 ft = 1 feet

b. Add depth of clean sand for separation (2a) at upslope edge, depth of rock layer (1 foot) to depth of cover (1 foot) to find the mound height at the upslope edge of rock layer;
1 ft + 1ft + 1ft = 3 feet

c. Enter table with landslope and upslope berm ratio. Select berm multiplier of 4.

d. Multiply berm multiplier by upslope mound height to find upslope berm width:
3 x 4 = 12 feet

e. Multiply rock layer width by by landslope to determine drop in elevation;
 x % ÷ 100 = feet

f. Add depth of clean sand for slope difference (2e) at downslope edge, to the mound height at the upslope edge of rock layer (2b) to find the downslope height;
 ft + ft = feet



g. Enter table with landslope and downslope berm ratio. Select berm multiplier of .

h. Multiply berm multiplier by downslope mound height to get downslope berm width:
3 x 4 = 12 feet

i. Compare the values of step G.1 and Step G.2h
 Select the greater of the two values as the downslope berm width; 12 feet

j. Total mound width is the sum of upslope berm (G.2d) width plus rock layer width (D.2) plus downslope berm width(G.2i);
12 ft + 10 ft + 12 ft = 34 feet

k. Total mound length is the sum of upslope berm width (G.2d) plus rock layer length (D.3) plus upslope berm width (G.2d);
12 ft + 50 ft + 12 ft = 74 feet



BERM SLOPE MULTIPLIERS

Land Slope, in %	DOWNSLOPE berm multipliers for various berm slope ratios					UPSLOPE berm multipliers for various berm slope ratios					
	3:1	4:1	5:1	6:1	7:1	3:1	4:1	5:1	6:1	7:1	8:1
0	3.0	4.0	5.0	6.0	7.0	3.0	4.0	5.0	6.0	7.0	8.0
1	3.09	4.17	5.26	6.38	7.53	2.91	3.85	4.76	5.66	6.54	7.41
2	3.19	4.35	5.56	6.82	8.14	2.83	3.70	4.54	5.36	6.14	6.90
3	3.30	4.54	5.88	7.32	8.86	2.75	3.57	4.35	5.08	5.79	6.45
4	3.41	4.76	6.25	7.89	9.72	2.68	3.45	4.17	4.84	5.46	6.06
5	3.53	5.00	6.67	8.57	10.77	2.61	3.33	4.00	4.62	5.19	5.71
6	3.66	5.26	7.14	9.38	12.07	2.54	3.23	3.85	4.41	4.93	5.41
7	3.80	5.56	7.69	10.34	13.73	2.48	3.12	3.70	4.23	4.70	5.13
8	3.95	5.88	8.33	11.54	15.91	2.42	3.03	3.57	4.05	4.49	4.88
9	4.11	6.25	9.09	13.04	18.92	2.36	2.94	3.45	3.90	4.30	4.65
10	4.29	6.67	10.00	15.00	23.33	2.31	2.86	3.33	3.75	4.12	4.44
11	4.48	7.14	11.11	17.65	30.43	2.26	2.78	3.23	3.61	3.95	4.26
12	4.69	7.69	12.50	21.43	43.75	2.21	2.70	3.12	3.49	3.80	4.08

Final Dimensions:
34 x 74



COUNTY OF BECKER

Environmental Services
Dan A. Holm, Administrator

829 Lake Avenue • P.O. Box 787
Detroit Lakes, MN 56502-0787 • Fax 218-846-7266

November 18, 1996

Mr. Bob Weinert
Rt 1 Box 232
Audubon, MN 56511

RE: Lot 3, Block 1 First Addition to Sugar Island

Dear Mr. Weinert:

I received confirmation from Jerdee Bridge Company that they will be installing a new drainfield on your property in the Spring of 1997.

In the meantime, please continue to have the septic tank pumped at regular intervals, and thank you for your attention to the matter.

Sincerely,

A handwritten signature in cursive script that reads "Joyce Cieluch".

Joyce Cieluch, Inspector
Environmental Services, Planning & Zoning

c: file

**JERDEE BRIDGE COMPANY
ROUTE 1, BOX 226
LAKE PARK, MN 56554
(218) 238-5132**

County of Becker
Environmental Services
Dan Holm, Adm.
829 Lake Ave.
Box 787
Detroit Lakes, MN 56502
FAX 218 846 7266

Attention: Joyce

This letter is to confirm that I will upgrade the ISTS on the Robert and Sue Weinert property in the Spring of 1997 to bring into compliance with statutes.

This will consist of design and installation of a new drainfield.

This property is located on Sugar Island of Little Cormorant Lake, Fire # A3534.

If you have any questions please contact me. Thank you.

Sincerely,

Edison V. D. Jerdee
Installer, DRP
License Number 1504



COUNTY OF BECKER

Environmental Services
Dan A. Holm, Administrator

829 Lake Avenue • P.O. Box 787
Detroit Lakes, MN 56502-0787 • Fax 218-846-7266

November 6, 1996

Mr. Bob Weinert
Rt 1 Box 232
Audubon, MN 56511

RE: Lot 3, Block 1 First Addition to Sugar Island


Dear Mr. Weinert:

This letter is intended to confirm our phone conversation regarding your non-conforming septic system that I observed on your property on November 5, 1996.

It is my understanding that you will be sending our office some sort of confirmation by a licensed sewer installer that you will be upgrading your system in the spring of 1997.

Your attention to this matter is greatly appreciated, I will keep a copy of this letter in your file should the office receive another complaint about the system.

Sincerely,


Joyce Cieluch, Inspector
Environmental Services, Planning & Zoning

c: file

Household Hazardous Waste
218-847-9664

Planning & Zoning
218-846-7314

Solid Waste Management
218-846-7310

Transfer Station
218-847-6382

CERTIFICATE OF COMPLIANCE
SEWAGE SYSTEM

This certificate has been issued this _____ day of _____, 19____,

to certify compliance with regulations of Zoning Ordinance, Becker County, Minnesota.

The premises covered by this certificate are legally described as: _____

Lake No. _____ Sec. _____ Twp. _____ Range _____ Twp. Name _____

Owner: Name _____


Address _____

Zip No. _____

Permit No. SP _____

Signed by: *Floyd Sherry*

Zoning Administrator
Becker County, Minnesota



APPLICATION FOR BUILDING OR SEWAGE PERMIT AND CERTIFICATE OF OCCUPANCY

12-7-30-31

LEGAL DESCRIPTION AND LOCATION
1811 NORTH STREET
1811 North Street, Detroit Lakes, MN 56501
 Lake No. 1 Lake Name Becker Lake Classification 1 Section 1 TWP. 1 Range 1 TWP. Name 1

IDENTIFICATION: Please Print All Information

Owner: John & Mary Smith
 Mailing Address: 1811 North Street, Detroit Lakes, MN 56501
 Zip No: 56501 Tel. No: 218-847-3938
 Contractor Name: John & Mary Smith
 Zip No: 56501 Tel. No: 218-847-3938

TYPE OF IMPROVEMENT: New Building Alteration
 RESIDENTIAL PROPOSED USE: One Family Dwelling Multiple Dwelling Units
 NON-RESIDENTIAL PROPOSED USE: Specify _____

ESTIMATED COST OF IMPROVEMENTS: \$ 100,000 Construction Starting Date: 11/11/17

PRINCIPAL TYPE OF FRAME: Wood Frame
 TYPE OF SEWAGE DISPOSAL: Individual Septic Tank, etc.
 WATER SUPPLY: Individual Well
 MECHANICAL EQUIPMENT: Elevator Air Conditioning Central
 DIMENSIONS: Basement Yes No
 Stories above basement: 1
 Sq. feet (outside dimension): 1,400
 Bedrooms: 3 Baths: 2
 HEATING: Electric Gas Oil Coal None Other

SEWAGE DISPOSAL SYSTEM DATA		SEPTIC TANK	SEEPAGE PITS	DRAIN FIELD
Capacity	<u>1,000</u> Gal.	<u>1,000</u> Gal.	<u>0</u> Sq. Ft.	<u>0</u> Sq. Ft.
Distance from nearest well	<u>75</u> Ft.	<u>75</u> Ft.	<u>0</u> Ft.	<u>0</u> Ft.
Distance from lake or stream	<u>75</u> Ft.	<u>75</u> Ft.	<u>0</u> Ft.	<u>0</u> Ft.
Distance from occupied building	<u>75</u> Ft.	<u>75</u> Ft.	<u>0</u> Ft.	<u>0</u> Ft.
Distance from property lines	<u>75</u> Ft.	<u>75</u> Ft.	<u>0</u> Ft.	<u>0</u> Ft.
Distance from bottom of water table	<u>75</u> Ft.	<u>75</u> Ft.	<u>0</u> Ft.	<u>0</u> Ft.

CHARACTERISTICS
 Lot Area is 1,400 square feet. Water frontage is 30 feet.
 Building set back from high water mark is 110 feet (Building Line).
 Land height above high water mark at building line is 10 feet.
 Building set back from State highway is 0 feet - from road or street is 0 feet.
 Side yard is 0 feet and 0 feet. Rear yard is 0 feet.
 Building will be located 0 feet from septic tank. (Sewage System Permit must be obtained before installation).
 Building will be located 0 feet from soil absorption system (Cesspool, Drainfield, etc.).

Agreement: I hereby certify that the information contained herein is correct and agree to do the proposed work in accordance with the description above set forth and according to the provisions of the ordinances of Becker County, Minnesota. I further agree that any plans and specifications submitted herewith shall become a part of this permit application. I also understand that this permit is valid for a period of six (6) months. Applicant further agrees that no part of the sewage system shall be covered until it has been inspected and accepted. It shall be the responsibility of the applicant for the permit to notify the County Zoning Administrator 48 hours before the job is ready for inspection.

Dated: 11/11/17 Signature of Owner: John & Mary Smith

Permit: Permission is hereby granted to the above named applicant to perform the work described in the above statement. This permit is granted upon the express condition that the person to whom it is granted, and his agent, employees and workmen shall conform in all respects to the ordinances of Becker County, Minnesota. This permit may be revoked at any time upon violation of said ordinances.

Dated: 11/11/17 Becker County Zoning Administrator: [Signature]
 Permit Fee \$ 0 State Surcharge \$ 0

Comments: _____

INSPECTOR'S CHECK LIST
Make all measurements and computations

	ACTUAL IS ↓	MINIMUM Shall Be ↓	Sq. Ft.
Building Set Back from High Water Mark	Ft.		Ft.
Building Set Back from State Highway	Ft.		Ft.
Side Yard	_____ & _____ Ft.	_____ & _____ Ft.	
Rear Yard	Ft.		Ft.
Elevation at Building Line above High Water Mark	Ft.		Ft.

SEWAGE DISPOSAL SYSTEM STATISTICS

Bed 1# x 34

CATEGORY	SEPTIC TANK				SEEPAGE BT				DRAIN FIELD			
	Actual		Should be		Actual		Should be		Actual		Should be	
Capacity	1000	Gls.		Gls.	374	S F		S F		S F		S F
Distance from Nearest Well	50	F		F	65	F	50	F		F	50	F
Distance from Lake or Stream	125	F		F	135	F		F		F		F
Distance from Occupied Building	15	F	10	F	15	F	10	F		F	20	F
Distance from Property Line	10	F	10	10	10	F	10	F		F	10	F
Distance from Bottom to Water Table	--	F	--	F	4	F	4	F		F	4	F

Inspector's Comments: *Al Dahl Installer, Heavy Clay sub soil*
Lat is of Washed Rock.

INTERPRETATION
OF ABBREVIATIONS
 Gls — Gallons
 SF — Square Feet
 F — Linear Feet

Dr. Ark Kuehne
Inspector's Signature

_____ Title

Inspection Dated 5-26 19 78

_____ Agency

BECKER COUNTY


SEWER PERMIT NUMBER 8347

ISSUED TO: Bob Weinert DATE: November 21, 1994

WORK AUTHORIZED in acceptance with application on file in the Becker County Zoning Office, site plan and following data:

WORK CATAGORY	SYSTEM	DESIGN	DATA
<input type="checkbox"/> NEW SYSTEM		TANK	DRAINFIELD
<input checked="" type="checkbox"/> REPAIR	DISTANCE TO WELL		*****
	DISTANCE TO BUILDING		20 FT +
ANTICIPATED USE	DISTANCE TO PROPERTY LINE		10 FT +
<input checked="" type="checkbox"/> SINGLE FAMILY	DISTANCE TO SUCTION LINE		50 FT +
<input type="checkbox"/> MULTIPLE FAMILY	DISTANCE TO PRESSURE LINE		10 FT +
<input type="checkbox"/> COMMERCIAL	DISTANCE TO LAKE/STREAM		75 FT +
<input type="checkbox"/> OTHER	TANK CAPACITY (GALLONS)		450 MINIMUM
	AREA OF DRAINFIELD (SQ FT)		4 FT +
	DEPTH TO WATER TABLE		

*****50 FT TO ALL WELLS WITH MORE THAN 50 FT OF CASING, 100 FT TO ALL WELLS WITH LESS THAN 50 FT OF CASING



Floyd Svenby P.A.
 Signature of Authorized Agent
 Permit Expires May 21, 1995

Zoning Administrator
 Title

November 21, 1994
 Date

PERMIT MUST BE DISPLAYED AT JOB SITE

NO CHANGES may be made to this permit without written approval from the Becker County Zoning Office. No system shall be covered without inspection. Please notify Becker County Zoning Office one (1) working day prior to time inspection is needed.

BECKER COUNTY


Building Permit No. 9-17883-31 Sewage System Permit No. _____

Township Audubon Sec. 32 Description SUGAR ISLAND - Lot - 3 - Block - 1

Work Authorized Addition to existing House 20x26' Deck 8x26'

TYPE OF IMPROVEMENT: () New Building () Alteration Other Addition to House
 RESIDENTIAL PROPOSED USE: One Family Dwelling () Multiple Dwelling Units _____
 NON-RESIDENTIAL PROPOSED USE: Specify: _____ Size: _____
 Stories ONE Basement Yes () No Bedrooms 2 Bathrooms 1 1/2

Issued to: Name Robert Weinert
 Address: Rt 1 - Box 129 - M Town Audubon
 State MN Zip 56511 Fire Number 193534



HORIZONTAL DISTANCE IN FEET FROM NEW CONSTRUCTION TO:

High Water Mark of Lake + 100'
 Side Lot Lines + 10'-10"
 Center Line of Public Road + 78'
 Road Right of Way _____
 Septic Tank _____ Drain Field _____
 Other _____

SEWAGE DISPOSAL SYSTEM DATA

	Septic Tank	Drain Field
Capacity <u>NEW IN 1978</u>	Gls.	Sq. Ft.
Distance from nearest well	Ft.	Ft.
Distance from lake or stream	Ft.	Ft.
Distance from occupied building	Ft.	Ft.
Distance from property line	Ft.	Ft.
Distance from bottom to Water Table	Ft.	Ft.

Lift Pump () Yes No

AGREEMENT: I HEREBY CERTIFY THAT THE INFORMATION CONTAINED HEREIN IS CORRECT AND AGREE TO DO THE PROPOSED WORK IN ACCORDANCE WITH THE DESCRIPTION ABOVE AND ACCORDING TO THE PROVISIONS OF THE ORDINANCE OF BECKER COUNTY. I AGREE TO POST THIS PERMIT ON THE PREMISES ON WHICH THE WORK IS TO BE DONE, AND MAINTAINED THERE UNTIL COMPLETION OF THE WORK. I AGREE THAT ANY VIOLATION OF THIS PERMIT OR THE BECKER COUNTY ZONING IS A MISDEMEANOR AND UPON CONVICTION THEREOF SHALL BE PUNISHED BY A FINE NOT TO EXCEED \$700.00 FOR EACH VIOLATION. NOTIFY THE BECKER COUNTY ZONING ADMINISTRATOR (847-4427) BEFORE BUILDING FOOTINGS HAVE BEEN COMPLETED. NO PART OF THE SEWAGE SYSTEM SHALL BE COVERED UNTIL IT HAS BEEN INSPECTED AND APPROVED. NOTIFY THE ZONING ADMINISTRATOR 24 HOURS BEFORE THE JOB IS READY FOR INSPECTION.

Robert Weinert
 SIGNATURE OF OWNER

Received By [Signature]
[Signature]
 Becker County Zoning Administrator

Date 6-22-89

BECKER COUNTY
 DETROIT LAKES, MN 56501

BECKER COUNTY

Sewage Permit No. SP No. _____

Location: Lake No. _____ Sec. _____ Twp. _____ Range _____ Twp. Name _____

Issued _____ 19____, To _____
Work Authorized _____

NOTE: This card must be placed in a conspicuous place not more than 12 feet above grade on the premises on which work is to be done, and must be maintained there until completion of such work. No part of system shall be covered until it has been inspected and approved. Notify Zoning Administrator, (847-3938) office when job is ready for inspection.



Becker County Zoning Administrator

BECKER COUNTY, MINNESOTA
Board of County Commissioners

